



***Enduring Resources***

475 17<sup>TH</sup> Street Suite 1500 Denver Colorado 80202  
Telephone 303 573-1222 Fax 303 573 0461

September 19, 2007

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P. O. Box 145801  
Salt Lake City, Utah 84114-5801

Attn.: Ms. Diana Mason

RE: Enduring Resources, LLC  
Hanging Rock 11-23-22-36  
SE-NW 36-11S-23E  
State Lease: ML-50085  
Uintah County, Utah

Dear Ms. Whitney:

Enclosed are two original applications to drill concerning the above-referenced proposed well. This information was also submitted to SITLA.

Enduring Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or additional information is required, please contact me at 303-350-5114.

Very truly yours,

**ENDURING RESOURCES, LLC**

Alvin R. (Al) Arlian  
Landman-Regulatory Specialist

ara  
Enclosures:

cc: SITLA w/ attachments

**RECEIVED**

**SEP 24 2007**

**DIV. OF OIL, GAS & MINING**

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

**APPLICATION FOR PERMIT TO DRILL**

<b>1A. TYPE OF WORK:</b> DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		<b>5. MINERAL LEASE NO:</b> ML-50085	<b>6. SURFACE:</b> State
<b>B. TYPE OF WELL:</b> OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>		<b>7. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>	
<b>2. NAME OF OPERATOR:</b> Enduring Resources, LLC		<b>8. UNIT or CA AGREEMENT NAME:</b>	
<b>3. ADDRESS OF OPERATOR:</b> 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220		<b>9. WELL NAME and NUMBER:</b> Hanging Rock 11-23-22-36	
<b>4. LOCATION OF WELL (FOOTAGES):</b> AT SURFACE: 1961' FNL - 2102' FWL AT PROPOSED PRODUCING ZONE: Same		<b>10. FIELD AND POOL, OR WILDCAT:</b> Undesignated	
<b>11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> SENW 36 11S 23E		<b>12. COUNTY:</b> Uintah	
<b>14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE:</b> 42 miles South of Bonanza, UT		<b>13. STATE:</b> UTAH	
<b>15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET):</b> 1961'	<b>16. NUMBER OF ACRES IN LEASE:</b> 640	<b>17. NUMBER OF ACRES ASSIGNED TO THIS WELL:</b> 40 acres	
<b>18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET):</b> 972'	<b>19. PROPOSED DEPTH:</b> 4,500	<b>20. BOND DESCRIPTION:</b> RLB0008031	
<b>21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.):</b> 5816' RT-KB	<b>22. APPROXIMATE DATE WORK WILL START:</b> 1/1/2008	<b>23. ESTIMATED DURATION:</b> 20 days	

**24. PROPOSED CASING AND CEMENTING PROGRAM**

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT			
20"	14" line pipe	40	3 yards	Ready Mix		
11"	8-5/8" J-55 24#	2,000	Premium Lead	183 sxs	3.50	11.1
			Premium Tail	183 sxs	1.15	15.8
7-7/8"	4-1/2" N-80 11.6#	4,500	Class G	48 sxs	3.30	11.0
			50/50 Poz Class G	420sxs	1.56	14.3

**25. ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER<br><input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN<br><input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |
|--|--|

NAME (PLEASE PRINT) Alvin R. (Al) Arlian TITLE Landman - Regulatory Specialist  
 SIGNATURE [Signature] DATE 9/19/2007

(This space for State use only)

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

API NUMBER ASSIGNED: 43-047-39651


APPROVAL:  
Date: 11-21-07  
By: [Signature]  
(See Instructions on Reverse Side)

**RECEIVED**  
**SEP 24 2007**

DIV. OF OIL, GAS & MINING

**T11S, R23E, S.L.B.&M.**


**ENDURING RESOURCES**



WELL LOCATION, HANGING ROCK  
 11-23-22-36, LOCATED AS SHOWN IN THE  
 SE 1/4 NW 1/4 OF SECTION 36, T11S,  
 R23E, S.L.B.&M. UTAH COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
 PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
 MADE BY ME OR UNDER MY SUPERVISION AND THAT  
 THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
 MY KNOWLEDGE AND BELIEF. No. 189377



◆ = SECTION CORNERS LOCATED  
 BASIS OF ELEV; U.S.G.S. 7-1/2 min  
 QUAD (ARCHY BENCH SE)

**HANGING ROCK 11-23-22-36**  
 (Surface Location) NAD 83  
 LATITUDE = 39° 49' 07.64"  
 LONGITUDE = 109° 17' 36.95"

**TRI STATE LAND SURVEYING & CONSULTING**  
 180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
 (435) 781-2501

DATE SURVEYED: 08-21-07	SURVEYED BY: D.G.	SHEET 2 OF 11
DATE DRAWN: 08-28-07	DRAWN BY: F.T.M.	
REVISED:	SCALE: 1" = 1000'	

Enduring Resources, LLC  
Hanging Rock 11-23-22-36  
SE-NW 36-11S-23E  
Uintah County, Utah  
State Lease: ML-50085

**ONSHORE ORDER 1 - DRILLING PLAN**

**1. Estimated Tops of Geological Markers:**

Formation	Depth (K.B.)
Uinta	Surface
Green River	229
Wasatch	2579
Mesaverde	4038

**2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:**

Substance	Formation	Depth (K.B.)
	KB-Uinta Elevation: 5816'	
Oil / Gas	Green River	229
Oil /Gas	Wasatch	2579
Oil /Gas	Mesaverde	4038
	Estimated TD	4500

A 11" hole will be drilled to approximately 2000 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

**3. Pressure Control Equipment: (3000 psi schematic attached)**

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

#### Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

#### E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

#### 4. Proposed Casing & Cementing Program:

##### A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
11"	8-5/8"	24#	J-55	ST&C	0 – 2,016' (KB) est.
7-7/8"	4-1/2"	11.6#	N-80	LT&C	0 – 4500' (KB)

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

**B. Casing Design Parameters:**

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension(mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	8-5/8", 24#/ft, J55, STC	1370/1.52(a)	2950/3.28(b)	244/5.81(c)
4500' (KB)	4-1/2", 11.6#/ft, N-80, LTC	6350/2.72 (d)	7780/3.62 (e)	223/4.97(f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

**PROPOSED CEMENTING PROGRAM**

**Surface Casing (if well will circulate)-Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
8-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	138	25%	11.1	3.50
8-5/8"	Tail	500	Premium cement + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	138	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft<sup>3</sup>/sx) cement will be premium cement w/ 3% CaCl<sub>2</sub>.+0.25 pps celloflake. Volume as required

**Surface Casing (if well will not circulate) - Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
8-5/8"	Lead	500	Premium cement + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	138	25	15.8	1.15
8-5/8"	Top job	As req.	Premium cement + 3% CaCl <sub>2</sub> + 0.25 pps celloflake	As Req.		15.8	1.15

**Production Casing and Liner** - Cemented TD to 300' above base of surface casing

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
4-1/2"	Lead	463	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	42	25	11.0	3.3
4-1/2"	Tail	2321	50/50 POZ Class G + 2% gel +1% CaCl <sub>2</sub> + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	424	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

**5. Drilling Fluids (mud) Program:**

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' - 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-4500' (KB)	8.8-9.8	8 - 10 ml	32-42	Water/Gel

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

**6. Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML  
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:  
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. **Abnormal Conditions:**

No abnormal temperatures or pressures are anticipated. No H<sub>2</sub>S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 2,340 psi (calculated at 0.52psi/foot of hole) and maximum anticipated surface pressure equals approximately 1,350 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. **Anticipated Starting Dates:**

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. **Variances:**

None anticipated

10. **Other:**


A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Single Shot directional surveys will be dropped every 2000 feet to monitor hole angle.




# ENDURING RESOURCES, LLC

## TYPICAL 3,000 p.s.i. BLOWOUT PREVENTER SCHEMATIC



## TYPICAL 3,000 p.s.i. CHOKE MANIFOLD SCHEMATIC



# **Enduring Resources, LLC**

## **Hanging Rock 11-23-22-36**

SE- NW-36- 11S-23E

Uintah County, Utah

State Lease: ML-50085

### **MULTI-POINT SURFACE USE & OPERATIONS PLAN**

#### **1. Existing Roads:**

##### **Directions to the Hanging Rock 11-23-22-36 Well Pad**

Beginning at the city of Vernal, Utah, head easterly on State Highway 40 for a distance of approximately  $\pm 4.0$  miles to the junction of this road and state road UT-45. Turn right and proceed southerly along state road UT-45 approximately  $\pm 36.0$  miles to the city of Bonanza. Leave the city of Bonanza heading south on state highway 45 for a distance of approximately 5.7 miles where there is a turn-off to the right. Turn right, leaving state highway 45, and proceed southwest for a distance of approximately 5.1 miles ( $3.2 + 1.9$  as shown on Topo "A"). The road then turns to the west; proceed northwesterly along said road for a distance of approximately 3.7 miles. Said road then turns to the southwest; proceed southwesterly then westerly for a distance of approximately 3.2 miles where the road forks. Turn left and bear southerly along the Asphalt Wash road for a distance of 3.0 miles where the road forks near a landing strip. Stay right, and continue south along the West Fork road for a distance of approximately 6.1 miles to the proposed access for the Hanging Rock 11-23-22-36 well pad. Turn left onto proposed access and continue west for approximately 2,710' to the proposed Hanging Rock 11-23-22-36 well pad.

#### **2. Planned Access Roads:**

The proposed access road will be approximately 2,770 feet of new construction all on-lease (*some of this access road may have already been constructed to access other SITLA wells on this same SITLA lease*). All off-lease access is on an existing county road (Asphalt Wash Road #4160).

**ALL NEW CONSTRUCTION IS ON SITLA LANDS.**

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

**3. Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):**

The following wells are wells located within a one (1) mile or greater radius of the proposed location.

- |    |       |  |
|----|-------|--|
| a. | None: | Water Wells:   |
| b. | None: | Injection Wells:   |
| c. | None: | Producing Wells:   |
| d. | None: | Drilling Wells:  |
| e. | None: | Shut-in Wells:   |
|    |       | McElvain-Hanging Rock Fed I1-4, NWNW-1-12S-23E           |
| f. | None: | Temporarily Abandoned Wells:                             |
| g. | None: | Disposal Wells:  |
| h. | None: | Abandoned Wells:   |
| i. | None: | Dry Holes:   |
| j. | None: | Observation Wells:                                       |
| k. | (9):  | Pending (staked) Wells:                                  |
|    |       | i. Enduring has nine other wells staked in this section. |
|    |       | ii. McElvain-Hanging Rock Fed 1-2, NWNE-1-12S-23E        |

**4. Location of Existing and/or Proposed Facilities:**

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be designated by DOG&M and SITLA. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline for this well will be:

2,719'	Surface Pipeline	On-Lease	SITLA
-0-	Surface Pipeline	Off-Lease	n/a

If this well is capable of economic production, a 4" (or less) steel surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately less than 2,719 feet of surface gas gathering pipeline shall be laid on the surface to minimize surface disturbance:

The proposed pipeline will begin at the well site; and be laid on the surface next to the new access road to tie-in to a steel surface pipeline that is located next to the county road.

The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

##### **5. Location and Type of Water Supply:**

Whenever practical, water will be obtained from Enduring Resources LLC Water Right Number 49-2215 or Water Right Number 49-2216 (\*See Townships of permitted Use below). If those sources are not available, a new water source shall be submitted prior to commencing operations. (These permits have one-year terms and then must be renewed)

\*Enduring Water Permits' Townships of Use:

T10S-R22E	T11S-R22E	T12S-R22E
T10S-R23E	<b><i>T11S-R23E</i></b>	T12S-R23E
T10S-R24E	T11S-R24E	T12S-R24E

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

**6 Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

**7. Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash well is burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

**8. Ancillary Facilities:**

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil stockpiles. Refer to Sheet 4.

**9. Well Site Layout: (Refer to Sheets #2, #3, and #4)**

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

**10. Plans for Surface Reclamation:**

**Producing Location:**

- a. Immediately upon well completion the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.
- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit and that portion of the location not needed for production facilities/operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

**Dry Hole/Abandoned Location:**

- i. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- ii. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

**Seed Mixture for Windrowed Top Soil Will Included:**

To be provided by the DOG&M and/or SITLA.

**11. Surface Ownership: Location, Access and Pipeline Route:**

Wellsite: SITLA

Access: SITLA

Pipeline: SITLA

**12. Other Information****On-site Inspection for Location, Access and Pipeline Route:**

The on-site will be scheduled by SITLA and DOG&M.

**Special Conditions of Approval:**

- Tanks and Production Equipment shall be painted Dark Olive Black.
- Surface Gathering Pipeline shall be 4" or less

**Archeology:**

- a. A Cultural Resource Inventory Report is pending and to be prepared by Montgomery Archaeological Consultants.

**Paleontology:**

- a. A Paleontology Reconnaissance Report is pending and to be prepared by Intermountain Paleo-Consulting.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.



**13, Lessee's or Operator's Representatives:****Representatives:**



Alvin R. (Al) Arlian  
Landman – Regulatory Specialist  
Enduring Resources, LLC  
475 17<sup>th</sup> Street, Suite 1500  
Denver, Colorado 80202  
Office Tel: 303-350-5114  
Cell Tel: 303-880-3841  
Fax Tel: 303-573-0461  
[aarlian@enduringresources.com](mailto:aarlian@enduringresources.com)

Doug Hammond  
Utah Superintendent  
Enduring Resources, LLC  
759 East 500 South  
Vernal, Utah 84078  
Office Tel: 435-781-0172  
Cell Tel: 435-790-6996  
Fax Tel: 435-781-0174  
[dhammond@enduringresources.com](mailto:dhammond@enduringresources.com)

**T11S, R23E, S.L.B.&M.**

**ENDURING RESOURCES**

**SECTION DRILLING MAP  
HANGING ROCK 11-23-22-36**



**LEGEND**

- = Vertical Well  
⊙ = Directional Well (Bottom Hole)


**TRI STATE LAND SURVEYING & CONSULTING**  
180 NORTH VERNAL AVE. — VERNAL, UTAH 84078  
(435) 781-2501

DATE SURVEYED: 08-21-07	SURVEYED BY: D.G.	SHEET 1 OF 11
DATE DRAWN: 08-28-07	DRAWN BY: F.T.M.	
REVISED:	SCALE: 1" = 1000'	

# ENDURING RESOURCES

## HANGING ROCK 11-23-22-36

Pad Location: SENW Section 36, T11S, R23E, S.L.B.&M.



### REFERENCE POINTS

230' SOUTHEAST = 5819.8'  
 280' SOUTHEAST = 5831.8'  
 175' NORTHEAST = 5800.5'  
 225' NORTHEAST = 5811.9'

SURVEYED BY: D.G. DATE SURVEYED: 08-21-07  
 DRAWN BY: F.T.M. DATE DRAWN: 08-28-07  
 SCALE: 1" = 60' REVISED:

Tri State

Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

(435) 781-2501

SHEET

3


OF 11

# ENDURING RESOURCES

## CROSS SECTIONS

### HANGING ROCK 11-23-22-36

Pad Location: SENW Section 36, T11S, R23E, S.L.B.&M.



NOTE:  
UNLESS OTHERWISE NOTED  
CUT SLOPES ARE AT 1:1  
FILL SLOPES ARE AT 1.5:1

#### ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)



ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	36,710	4,360	Topsoil is not included in Pad Cut	32,350
PIT	4,550	0		4,550
TOTALS	41,260	4,360	2,160	36,900

SURVEYED BY: D.G. DATE SURVEYED: 08-21-07  
DRAWN BY: F.T.M. DATE DRAWN: 08-28-07  
SCALE: 1" = 60' REVISED:

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

SHEET  
4  
OF 11

*Pad Location: SENW Section 36, T11S, R23E, S.L.B.&M.*



FLAR  
PIT

Note:  
Flare pit is to be  
located at least 100'  
from well head.

Proposed Access Road for the 11-23-32-36

PROPOSED —  
ACCESS ROAD

SURVEYED BY: D.G.	DATE SURVEYED: 08-21-07
DRAWN BY: F.T.M.	DATE DRAWN: 08-28-07
SCALE: 1" = 60'	REVISED:

**Tri State** (435) 781-2501  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078



SHEET  
5  
OF 11

# ENDURING RESOURCES

## PRODUCTION SCHEMATIC

### HANGING ROCK 11-23-22-36

Pad Location: SENW Section 36, T11S, R23E, S.L.B.&M.




Note:  
Flare pit is to be  
located at least  
100' from well head.

SURVEYED BY: D.G.	DATE SURVEYED: 08-21-07
DRAWN BY: F.T.M.	DATE DRAWN: 08-28-07
SCALE: 1" = 60'	REVISED:

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

SHEET  
6  
OF 11





**ENDURING RESOURCES**

**Hanging Rock 11-23-22-36**  
**Sec. 36, T11S, R23E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501

180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw

DATE: 09-10-2007

**Legend**

Existing Road  
 Proposed Access

**TOPOGRAPHIC MAP**


**"B"**

**SHEET**

**8**

**OF 10**





**ENDURING RESOURCES**

**Hanging Rock 11-23-22-36**  
**Sec. 36, T11S, R23E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*

(435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 : 100,000

DRAWN BY: mw

DATE: 09-10-2007

**Legend**


Existing Road  
 Proposed Access

TOPOGRAPHIC MAP

**"A"**

SHEET  
**7**  
 OF 10





**ENDURING RESOURCES**

**Hanging Rock 11-23-22-36**  
**Sec. 36, T11S, R23E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*

(435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw

DATE: 09-10-2007

**Legend**

- Location
- One-Mile Radius

**TOPOGRAPHIC MAP**

**"C"**

**SHEET**

**9**

**OF 10**





## ENDURING RESOURCES

**Hanging Rock 11-23-22-36**  
**Sec. 36, T11S, R23E, S.L.B.&M.**



**Tri-State**  
Land Surveying Inc.

(435) 781-2501

180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: mw

DATE: 09-10-2007

### Legend

## Roads

**Proposed Gas Line**

**TOPOGRAPHIC MAP**

"D"

SHEET

10  
OF 10





CENTER STAKE

  
ENDURING RESOURCES  
H.R. 11-23-22-36

Date Photographed: 08/21/2007  
Date Drawn: 09/14/2007  
Drawn By: mw

  
*Tri-State*  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078





NORTH

  
ENDURING RESOURCES  
H.R. 11-23-22-36

Date Photographed: 08/21/2007

Date Drawn: 09/14/2007


Drawn By: mw

  
Tri-State  
Land Surveying Inc.  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

EAST







SOUTH

  
 ENDURING RESOURCES  
 H.R. 11-23-22-36

Date Photographed: 08/21/2007

Date Drawn: 09/14/2007

Drawn By: mw

  
 Tri-State  
 Land Surveying Inc.  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

WEST



**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 09/24/2077

API NO. ASSIGNED: 43-047-39651

WELL NAME: HANGING ROCK 11-23-22-36

OPERATOR: ENDURING RESOURCES, LLC ( N2750 )

PHONE NUMBER: 303-350-5114

CONTACT: AL ARLIAN

PROPOSED LOCATION:

SE NW 36 110S 230E

SURFACE: 1961 FNL 2102 FWL

BOTTOM: 1961 FNL 2102 FWL

COUNTY: UINTAH

LATITUDE: 39.81879 LONGITUDE: -109.2929

UTM SURF EASTINGS: 646109 NORTHINGS: 4408829

FIELD NAME: UNDESIGNATED ( 2 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DWV	11/21/07
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-50085

SURFACE OWNER: 3 - State

PROPOSED FORMATION: MVRD

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. RLB0008031 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
(No. 49-2216 )  
☒ RDCC Review (Y/N)  
(Date: )  
☒ Fee Surf Agreement (Y/N)  
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

☐ R649-2-3.  
Unit: \_\_\_\_\_  
☒ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
☐ R649-3-3. Exception  
☐ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
☐ R649-3-11. Directional Drill

COMMENTS: Needs Permit (10-24-07)

STIPULATIONS: 1- Spacing Slip  
2- STATEMENT OF BASIS  
3- Surface Csg Cont Slip





# Application for Permit to Drill

## Statement of Basis

10/29/2007

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Ownr</b>	<b>CBM</b>
564	43-047-39651-00-00		GW	S	No
<b>Operator</b>	ENDURING RESOURCES, LLC		<b>Surface Owner-APD</b>		
<b>Well Name</b>	HANGING ROCK 11-23-22-36		<b>Unit</b>		
<b>Field</b>	UNDESIGNATED		<b>Type of Work</b>		
<b>Location</b>	SENW 36 11S 23E S 1961 FNL 2102 FWL GPS Coord (UTM) 646109E 4408829N				

### Geologic Statement of Basis

Enduring proposes to set 2,000 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at 2,700 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 36. The surface formation at this location is the Uinta/Green River Formation transition. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The Green River Formation is made up of interbedded limestones, shales and sandstones. Fresh water aquifers can be found in the Green River Formation and should be protected. The proposed surface casing should adequately protect any potentially useable aquifers. Production casing cement should be brought up above the base of the moderately saline ground water.

Brad Hill

10/29/2007

APD Evaluator

Date / Time

### Surface Statement of Basis

The location is in the West Fork of Asphalt Draw, approximately 27 road miles south west of Bonanza Ut, and approximately 65 miles southeast of Vernal, UT. Access from Vernal, UT is by Utah State Highways, Uintah County and existing oilfield development roads to where approximately 2,710 feet of additional road will be constructed.

Topography in the general area is broad canyon bottoms separated by frequently steep and often ledgey side-slopes, which top-out onto often broad ridge tops. Frequent outwash plains and deposits occur along the sides of the major bottoms. West Fork of Asphalt Wash is a broad somewhat gentle alluvial wash, which is dry except for spring runoff and sometimes-intense summer rainstorms. No seeps springs or streams are known to exist in the immediate area. An occasional pond constructed for livestock and wildlife watering occurs. The White River is approximately 10 miles down-drainage to the north.

The proposed Hanging Rock 11-23-22-36 gas well is in a moderately narrow gently sloping draw. The draw runs from the north with a swale forking off to the southeast. The draw is bordered by moderately steep side slopes, which are rimmed with exposed sandstone bedrock near the tops. The west side of the location as laid out, cuts into a steep side-slope. The location was sized and laid out for drilling to the deeper Mesa Verde formation. The well will be drilled to the Wasatch formation and will not require as large of reserve pit as designed. The reserve pit side of the location will be reduced 25 feet and the length of the pit reduced to 100 feet. This reduction in width will bring the cut partially off this steep sideslope. The bottom of the draw shows little evidence of seasonal runoff however some may occur. The location completely blocks any down drainage flow. If the well is drilled during the summer season when intense rainstorms may occur, a catchment pond should be constructed up draw next to the location. After the well is drilled, a diversion can be constructed on the north side of the pad to channel any flows that may occur.

Jim Davis of SITLA and Ben Williams representing the UDWR attended the presite.

Mr. Williams stated the area is classified as high value winter habitat for both deer and elk. To reduce the disturbance to these species during this critical period, he recommended to Mr. Hammond and Mr. Davis a



---

# Application for Permit to Drill

## Statement of Basis

10/29/2007

Utah Division of Oil, Gas and Mining

Page 2

restriction period from November 15 to April 15th where no construction or drilling including work-over rigs occur. Mr. Williams also gave Mr. Hammond and Mr. Davis a copy of this evaluation and also a seed mix recommendation to be used when the reserve pit and location are reclaimed.

Floyd Bartlett  
Onsite Evaluator

10/24/2007  
Date / Time

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** ENDURING RESOURCES, LLC  
**Well Name** HANGING ROCK 11-23-22-36  
**API Number** 43-047-39651-0 **APD No** 564 **Field/Unit** UNDESIGNATED  
**Location:** 1/4,1/4 SENW **Sec** 36 **Tw** 11S **Rng** 23E 1961 FNL 2102 FWL  
**GPS Coord (UTM)** 646115 4408839 **Surface Owner**

### **Participants**

Floyd Bartlett (DOGM), Douglas Hammond (Enduring Resources), Mike Stewart (Ponderosa Oilfield Services), Jim Davis (SITLA), Ben Williams (UDWR), Dustin Gardner and Ryan Reese (TRI-State Land Surveying and Consulting)

### **Regional/Local Setting & Topography**

The location is in the West Fork of Asphalt Draw, approximately 27 road miles south west of Bonanza Ut, and approximately 65 miles southeast of Vernal, UT. Access from Vernal, UT is by Utah State Highways, Uintah County and existing oilfield development roads to where approximately 2,710 feet of additional road will be constructed.

Topography in the general area is broad canyon bottoms separated by frequently steep and often ledgey side-slopes, which top-out onto often broad ridge tops. Frequent outwash plains and deposits occur along the sides of the major bottoms. West Fork of Asphalt Wash is a broad somewhat gentle alluvial wash, which is dry except for spring runoff and sometimes-intense summer rainstorms. No seeps springs or streams are known to exist in the immediate area. An occasional pond constructed for livestock and wildlife watering occurs. The White River is approximately 10 miles down-drainage to the north.

The proposed Hanging Rock 11-23-22-36 gas well is in a moderately narrow gently sloping draw. The draw runs from the north with a swale forking off to the southeast. The draw is bordered by moderately steep side slopes, which are rimmed with exposed sandstone bedrock near the tops. The west side of the location as laid out, cuts into a steep side-slope. The location was sized and laid out for drilling to the deeper Mesa Verde formation. The well will be drilled to the Wasatch formation and will not require as large of reserve pit as designed. The reserve pit side of the location will be reduced 25 feet and the length of the pit reduced to 100 feet. This reduction in width will bring the cut partially off this steep sideslope. The bottom of the draw shows little evidence of seasonal runoff however some may occur. The location completely blocks any down drainage flow. If the well is drilled during the summer season when intense rainstorms may occur, a catchment pond should be constructed up draw next to the location. After the well is drilled, a diversion can be constructed on the north side of the pad to channel any flows that may occur.

Both the minerals and surface are owned by SITLA.

### **Surface Use Plan**

#### **Current Surface Use**

Grazing  
Recreational  
Wildlife Habitat  
Deer Winter Range

#### **New Road**

Miles	Well Pad	Src Const Material	Surface Formation
0.5	Width 225 Length 355	Onsite	UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate? Y**

## Environmental Parameters

### **Affected Floodplains and/or Wetland N**

#### **Flora / Fauna**

Vegetation consists primarily of big sagebrush.

Deer , elk , coyotes, rabbits, sheep and cattle during the winter, small mammals and birds.

#### **Soil Type and Characteristics**

Moderately deep sandy loam.

#### **Erosion Issues N**

#### **Sedimentation Issues Y**

The location completely blocks any down drainage flow.

#### **Site Stability Issues N**

#### **Drainage Diversion Required Y**

After the well is drilled, a diversion can be constructed on the north side of the pad to channel any flows that may occur

#### **Berm Required? N**

#### **Erosion Sedimentation Control Required? Y**

If the well is drilled during the summer season when intense rainstorms may occur, a catchment pond should be constructed up draw next to the location.

**Paleo Survey Run? Y      Paleo Potential Observed? N      Cultural Survey Run? Y      Cultural Resources? N**

## Reserve Pit

### **Site-Specific Factors**

### **Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	300 to 1320	10
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>	10 to 20	5
<b>Affected Populations</b>	<10	0
<b>Presence Nearby Utility Conduits</b>	Not Present	0

**Final Score      30      1      Sensitivity Level**

### **Characteristics / Requirements**

The size of the pit will be reduced from what is shown on Sheet 3 of the APD. It is planned to be 50' by 100' and 12' deep in an area of cut on the southeast corner of the location. No stabilization problems are expected.  
A 16 mil liner will be required.

**Closed Loop Mud Required? N      Liner Required? Y      Liner Thickness 16      Pit Underlayment Required? Y**

**Other Observations / Comments**

ATV's were used to access the site.

Floyd Bartlett  
**Evaluator**

10/24/2007  
**Date / Time**

# 2007-11 Enduring Hanging Rock 11-23-22-36

## Casing Schematic

BHP  $0.052(4500)9.8 = 2293 \text{ psi}$   
anticipate 2340 psi

Gas  $.12(4500) = 540$   
 $2293 - 540 = 1753 \text{ psi, MASP}$

BOPE 3M ✓

Burst 2950  
70% 2065 psi

Max P @ surf. shoe  
 $.22(2484) = 546$   
 $2293 - 546 = 1747 \text{ psi}$   
8-5/8" MW 8.4  
Frac 19.3

test to 1750 psi ✓

Stop surf. cont. ✓

✓ Adequate ✓

11/21/07

Surface

12 1/2"

15 1/2"

Uinta

229' Green River

TOC @  
766.

✗ surface stop ✓

1755' TOC w/ 9% w/o

TOC @  
1951.  
Surface  
2016. MD

2579' Wasatch

2700' ± BMSW

4038' Mesaverde

4-1/2"  
MW 9.8

Production  
4500. MD

Well name:	<b>2007-11 Enduring Hanging Rock 11-23-22-36</b>	
Operator:	<b>Enduring Resource, LLC</b>	Project ID:
String type:	Surface	43-047-39651
Location:	Uintah County	

**Design parameters:**
**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 103 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 266 ft

Cement top: 766 ft

**Burst**

Max anticipated surface pressure: 1,751 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 1,993 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.  
Neutral point: 1,762 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 4,500 ft  
Next mud weight: 9.800 ppg  
Next setting BHP: 2,291 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,016 ft  
Injection pressure: 2,016 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2016	8.625	24.00	J-55	ST&C	2016	2016	7.972	720.9

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	880	1370	1.557	1993	2950	1.48	42	244	5.77 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: November 15, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2016 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2007-11 Enduring Hanging Rock 11-23-22-36</b>	
Operator:	<b>Enduring Resource, LLC</b>	Project ID:
String type:	Production	43-047-39651
Location:	Uintah County	

**Design parameters:**
**Collapse**

Mud weight: 9.800 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 138 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 1,951 ft

**Burst**

Max anticipated surface pressure: 1,301 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 2,291 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.  
Neutral point: 3,841 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4500	4.5	11.60	N-80	LT&C	4500	4500	3.875	392.7

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2291	6350	2.772	2291	7780	3.40	45	223	5.01 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801-538-5357  
FAX: 801-359-3940

Date: November 15, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 4500 ft, a mud weight of 9.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**From:** Ed Bonner  
**To:** Mason, Diana  
**Date:** 10/18/2007 3:01 PM  
**Subject:** Well Clearance

**CC:** Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

Enduring Resources, LLC

Hanging Rock 11-23-23-36 (API 43 047 39648)  
Hanging Rock 11-23-32-36 (API 43 047 39649)  
Hanging Rock 11-23-33-36 (API 43 047 39650)  
Hanging Rock 11-23-22-36 (API 43 047 39651)  
Hanging Rock 11-23-31-36 (API 43 047 39656)  
Hanging Rock 11-23-21-36 (API 43 047 39657)

Kerr McGee Oil & Gas Onshore LP

NBU 1022-14A (API 43 047 39524)  
NBU 1021-20H (API 43 047 39525)  
NBU 1021-20G (API 43 047 39526)  
NBU 1021-20F (API 43 047 39527)  
NBU 1021-20E (API 43 047 39528)  
NBU 1021-20D (API 43 047 39529)  
NBU 1021-20B (API 43 047 39530)  
NBU 1021-20O (API 43 047 39531)  
NBU 1021-20L (API 43 047 39532)  
NBU 1021-20K (API 43 047 39533)  
NBU 1021-20J (API 43 047 39534)

Medallion Exploration

Atchee Ridge 2-20 (API 43 047 39517)  
Atchee Ridge 11-20 (API 43 047 39518)  
Atchee Ridge 6-20 (API 43 047 39519)  
Atchee Ridge 7-20 (API 43 047 39520)  
Atchee Ridge 3-20 (API 43 047 39521)

If you have any questions regarding this matter please give me a call.





JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil Gas and Mining

JOHN R. BAZA  
Division Director

November 21, 2007

Enduring Resources, LLC  
475 17th St., Ste. 1500  
Denver, CO 80202

Re: Hanging Rock 11-23-22-36 Well, 1961' FNL, 2102' FWL, SE NW, Sec. 36, T. 11 South, R. 23 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39651.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
SITLA

Operator: Enduring Resources, LLC  
Well Name & Number Hanging Rock 11-23-22-36  
API Number: 43-047-39651  
Lease: ML-50085

Location: SE NW      Sec. 36      T. 11 South      R. 23 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at:           (801) 538-5338 office           (801) 942-0873 home
- Carol Daniels at:       (801) 538-5284 office
- Dustin Doucet at:      (801) 538-5281 office           (801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
7. Surface casing shall be cemented to the surface.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

CONFIDENTIAL

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-50085
2. NAME OF OPERATOR: Enduring Resources, LLC	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202	7. UNIT or CA AGREEMENT NAME: n/a
PHONE NUMBER: (303) 350-5719	8. WELL NAME and NUMBER: Hanging Rock 11-23-22-36
10. FIELD AND POOL, OR WILDCAT: Undesignated	9. API NUMBER: 4304739651

4. LOCATION OF WELL FOOTAGES AT SURFACE: 1961' FNL - 2102' FWL COUNTY: Uintah QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENW 36 11S 23E S STATE: UTAH
--

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____  <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: Request for APD Extension

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill ....

FROM: 11/21/2008  
TO: 11/21/2009

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 11-25-08  
By: [Signature]

NAME (PLEASE PRINT) Alvin R. (Al) Arlian	TITLE Landman - Regulatory Specialist
SIGNATURE [Signature]	DATE 11/10/2008

(This space for State use only)

COPY SENT TO OPERATOR

Date: 11-26-2008

Initials: KS

(5/2000)

(See Instructions on Reverse Side)

RECEIVED

NOV 24 2008

DIV. OF OIL, GAS & MINING



**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304739651  
**Well Name:** Hanging Rock 11-23-22-36  
**Location:** 1961' FNL - 2102' FWL, SENW, Sec 36, T11S-R23E  
**Company Permit Issued to:** Enduring Resources, LLC  
**Date Original Permit Issued:** 11/21/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

11/10/2008  
Date


Title: Administrative Assistant

Representing: Enduring Resources, LLC

**RECEIVED**

**NOV 24 2008**

**DIV. OF OIL, GAS & MINING**

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-50085			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> Enduring Resources, LLC		<b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>3. ADDRESS OF OPERATOR:</b> 475 17th Street, Suite 1500 , Denver, CO, 80202		<b>8. WELL NAME and NUMBER:</b> HANGING ROCK 11-23-22-36			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1961 FNL 2102 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 36 Township: 11.0S Range: 23.0E Meridian: S		<b>9. API NUMBER:</b> 43047396510000			
<b>PHONE NUMBER:</b> 303 350-5114 Ext		<b>9. FIELD and POOL or WILDCAT:</b> OIL SPRINGS			
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/25/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input checked="" type="checkbox"/> APD EXTENSION          OTHER:       </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  Requesting an one-year extension to APD expiration date.					
<p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: <u>November 24, 2009</u></p> <p style="color: red; font-weight: bold;">By: <u></u></p>					
<b>NAME (PLEASE PRINT)</b> Alvin Arlian		<b>PHONE NUMBER</b> 303 350-5114			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Landman-Regulatory			
<b>DATE</b> 11/24/2009					



## The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

### Request for Permit Extension Validation Well Number 43047396510000

**API:** 43047396510000

**Well Name:** HANGING ROCK 11-23-22-36

**Location:** 1961 FNL 2102 FWL QTR SENW SEC 36 TWNP 110S RNG 230E MER S

**Company Permit Issued to:** ENDURING RESOURCES, LLC

**Date Original Permit Issued:** 11/21/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Signature:** Alvin Arlian


**Date:** 11/24/2009

**Title:** Landman-Regulatory **Representing:** ENDURING RESOURCES, LLC

**Date:** November 24, 2009

**By:** 

**RECEIVED** November 24, 2009



# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER

*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA

*Division Director*

November 18, 2010

Al Arlian  
Enduring Resources, LLC  
475-17<sup>th</sup> Street, Ste. 1500  
Denver, CO 80202

Re: APD Rescinded – Hanging Rock 11-23-22-36, Sec.36 T.11S, R.23E  
Uintah County, Utah API No. 43-047-39651


Dear Mr. Arlian:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on November 21, 2007. On November 25, 2008 and November 24, 2009 the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective November 18, 2010.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

  
Diana Mason  
Environmental Scientist

cc: Well File  
Ed Bonner, SITLA

